## **ADDENDUM NO. 1**

TO

## **GENERAL SPECIFICATIONS**

## **FOR**

## **CLEANING & INSPECTION OF POTASH, BRIGHAM HILL AND MURPHY TANKS**

This Addendum No. 1 forms a part of the Contract Documents and modifies the Bidding Documents posted as noted below. Acknowledge receipt of this Addendum in the space provided in the FORM FOR "BID PROPOSAL". Failure to do so may subject the Bidder to disqualifications. This Addendum consists of 1 page.

1. Updated 1.1 General to include more information about the tanks:

The work herein specified to be done under this section shall consist of furnishing all equipment, labor and materials to provide an internal inspection of tanks and removal of 1-3 inches of sand/silt. All tanks have static mixing and no baffles. Contractor will provide a report on the internal conditions of each tank. Report will include photographs/video. Any work under consideration may be omitted at the option of the OWNER.

Specifically, the tanks to be cleaned and redeveloped are to be as follows:

	TYPE	DIAMETER	HEIGHT	SQ FT	<mark>Approx</mark>
					<b>Location</b>
1. Potash	90' El. Tower	90	40	6,362	Coolidge St.
2. Brigham	OG Concrete	124	22	12,070	Forbes Rd.
3. Murphy	OG Welded	66	40	3,419	Crestview Dr.
4. Popes	OG Welded	80	37	5,026	Bellview St.
5. Lakeview	OG Welded	41.5	50	1,352	Saratoga Dr.

\*\*\*\*END OF ADDENDUM 1\*\*\*\*\*